BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2012-13/RD/WORK_INDENT4847/CALL-2

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/05/2014-15, Date:17.07.2014

Construction of RCC drain at Ayappa swamy temple in ward no. 07, Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of SAMBASHIVA	
				In Figures	In Words
1	81	Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods Complete as per Specification and Directions of Engineer in charge of the Work	Cum	66.00	Rupees Sixty Six Only
2	234	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and slectrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking Complete as per Specification and Directions of Engineer in charge of the Work	Cum	227.91	Rupees Two Hundred Twenty Seven and Ninety One Paise Only
3	17.55	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15cms. thick well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per Specification and Directions of Engineer in charge of the Work	Cum	4135.99	Rupees Four Thousand One Hundred Thirty Five and Ninety Nine Paise Only
4	42.12	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459cum, with superplastisiser @ 3lts confirming to IS 9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses. parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc..,including cost of all materials, labour, HOM of machinery, curing, Complete as per Specification and Directions of Engineer in charge of the Work	Cum	5561.06	Rupees Five Thousand Five Hundred Sixty One and Six Paise Only
5	42.12	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5 m including cost of all labour Complete as per Specification and Directions of Engineer in charge of the Work	Cum	102.05	Rupees One Hundred Two and Five Paise Only

6	16.85	Providing T.M.T steel reinforcement for R.C.C work including straightening cutting, bending, hooking, placing wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of ,materials, labor HOM of machinery Complete as per Specification and Directions of Engineer in charge of the Work	Qtl	7714.48	Rupees Seven Thousand Seven Hundred Fourteen and Forty Eight Paise Only
7	117	Providing and laying 10cms thick precast R.C.C. slabs (DATA RATE) Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	1574.85	Rupees One Thousand Five Hundred Seventy Four and Eighty Five Paise Only
8	444.6	Providing and removing centering, shuttering, shuttering, strutting, propping etc.., and removal of form work for vertical surface such as walls at any thickness, including attached plasters, buttresses, plinth and string courses cost of all materials, labour Complete as per Specification and Directions of Engineer in charge of the Work	Sqm	232.45	Rupees Two Hundred Thirty Two and Forty Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92